

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22760-00-00  
Spot: W2W2NE Sec/Twnshp/Rge: 2-32S-13W  
1320 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: SILL Well #: A 2  
County: BARBER Total Vertical Depth: 4601 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	307		WITH 210 SX CMT
PROD	4.5	4415	3108	WITH 135 SX CMT <b>149.53</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2009 2:30 PM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: THADD STAR Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: PLACE 50' SAND PLUG OVER PERFS & 4 SX CMT. PLUG AT 660' WITH 12 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2009 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4260' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 660' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4297	4304		

INVOICED  
9/28/09  
INV NO 2010060262  
KANSAS CORPORATION COMMISSION  
AUG 14 2009  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

*Stephen J Pfeifer*  
(TECHNICIAN)

RECEIVED

JUL 29 2009

KCC DODGE CITY