

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22763-00-01
Spot: W2NWNWNW Sec/Twnshp/Rge: 23-31S-13W
4950 feet from S Section Line, 5175 feet from E Section Line
Lease Name: PACKARD Well #: D1
County: BARBER Total Vertical Depth: 4485 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3340		
CIBP		3500		
SURF	8.625	306		WITH 225 SX CMT
PROD	4.5	4306	2613	WITH 125 SX CMT

145.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2009 2:00 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THADD STAR Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: PLACE 50' SAND PLUG OVER PERFS & 4 SX CMT. PLUG AT 660' WITH 12 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2009 8:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3220' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 660' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3658	3668		LOWER DOUGLAS
3359	3364		LECOMPTON
3306	3312		LECOMPTON

KANSAS CORPORATION COMMISSION
AUG 14 2009
RECEIVED

INVOICED
9/28/09
2010060262

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JUL 29 2009

Signed Stephen P Pfeifer
(TECHNICIAN)

KCC DODGE CITY