

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21233-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 3-7S-29W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: PORSCH "B" Well #: 1-3
County: SHERIDAN Total Vertical Depth: 4530 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		

147.23

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2009 3:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LARRY PICKNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 08/07/2009 4:30 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 4465' w/25 wxs.
2nd. Plug at 2500' w/25 sxs.
3rd. Plug at 1590' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

9/28/09
2010060271

RECEIVED
AUG 17 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce D. Basye
(TECHNICIAN)

CM

Form CP-2/3

AUG 11 2009