

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21066-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 29-29S-38W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: W B SCHERLING Well #: 29-1
County: GRANT Total Vertical Depth: 5927 feet

Operator License No.: 32309
Op Name: PRESCO WESTERN LLC
Address: 5665 FLATIRON PKWY
BOULDER, CO 80301

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5620		WITH 2 SX CMT
SURF	8.625	1831		WITH 815 SX CMT 192.63
COND	20	40		WITH 6 SX CMT
DVT		2879		WITH 240 SX CMT
PROD	5.5	5926	0	WITH 655 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2009 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STEVE RIDENOUR Company: PRESCO WESTERN Phone: (620) 655-3459

Proposed Plugging Method: CIBP @ 5620' WITH 2 SX CMT. 20 SX CMT AT 2890'. SHOOT SQUEEZE PERFFS @ +/-1860'. CIRCULATED CMT TO SURFACE. LEAVE 50 SX CMT IN CASING. 50 SX CMT AT +/- 600'.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2009 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5620' & 2 SX CMT. 1ST PLUG AT 2902' WITH 20 SX CMT. 2ND PLUG PERFORATE 5 1/2" @ 1860'. PUMPED 440 SX CMT. FILLED 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
5667	5674		

KANSAS CORPORATION COMMISSION

AUG 14 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED

JUL 28 2009

KCC DODGE CITY

Signed

Jack MacLuskey
(TECHNICIAN)