

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20781-00-00  
Spot: S2SEW Sec/Twnshp/Rge: 23-16S-42W  
2217 feet from N Section Line, 1890 feet from W Section Line  
Lease Name: BARBARA Well #: 1-23  
County: GREELEY Total Vertical Depth: 5170 feet

Operator License No.: 3581  
Op Name: RED OAK ENERGY, INC.  
Address: 7701 E KELLOGG DR STE 710 PO BOX  
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1935		
CIBP		4715		WITH 2 SX CMT
SURF	8.625	356		WITH 285 SX CMT
PC		1944		WITH 780 SX CMT
PROD	4.5	5164	0	WITH 150 SX CMT

168.03

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2009 9:30 AM  
Plug Co. License No.: 34249 Plug Co. Name: SANJEL (USA) INC.  
Proposal Rcvd. from: SHANE PELTON Company: RED OAK ENERGY Phone: (316) 652-7373

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/22/2009 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG CIBP @ 4715' WITH 2 SX CMT. 2ND PLUG SET CIBP @ 1935'. TEST CASING TO 800#. 3RD PLUG FILL CASING FROM 1900-0' WITH 145 SX CMT. 4TH PLUG PRESSURE TESTED ANNULUS TO 700#.

Perfs:

Top	Bot	Thru	Comments
5053	5056		
5028			
4979	4984		

KANSAS CORPORATION COMMISSION  
AUG 14 2009  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SANJEL.

Plugged through: CSG

District: 01

RECEIVED  
JUL 29 2009

Signed [Signature]  
(TECHNICIAN)

KCC DODGE CITY

9/28/09  
2010060278