

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21396-00-00
Spot: NESENE Sec/Twnshp/Rge: 35-16S-29W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: GILL Well #: 1
County: LANE Total Vertical Depth: 4630 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		WITH 150 SX CMT
PROD	4.5	4518	0	WITH 200 SX CMT 150.48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2009 2:15 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS & 2 SX CMT. RUN TBG TO 2100' & CIRCULATE CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2009 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PER KCC RECORDS: PERFORATED @ 2160' & CIRCULATED 450 SX CMT TO 275'. SAND BACK TO 4273' & 2 SX CMT. RUN TBG TO 2173'. CIRCULATE CMT FROM 2173' TO 0' USING 150 SX CMT. STAYED FULL. PUMPED 50 SX CMT DOWN ANNULUS. SHUT IN PRESSURE 200 PSI. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4278	4281		
9/28/09 201006028			
KANSAS CORPORATION COMMISSION AUG 14 2009 RECEIVED			

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed *Ken Jehlik* (TECHNICIAN)

RECEIVED

JUL 28 2009

KCC DODGE CITY

Form CP-203