

15-051-04330-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 10 Twp. 12 Rge. 16 (E) (W) x

Location as "NE/CNW/SW" or footage from lines SW NE SW

Lease Owner Leo J. Dreiling Oil Company

Lease Name Dickinson "D" Well No. 1

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D. & A.

Date well completed 2/25/64 19

Application for plugging filed 2/25/64 19

Application for plugging approved 2/25/64 19


Plugging commenced 2/25/64 19

Plugging completed 2/25/64 19

Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0-19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3429' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	187'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filling hole with rotary mud to a depth of 420' were 1st plug was set using 20 sacks cement, filling hole with rotary mud to a depth of 160' were 2nd plug was set using 20 sacks cement, filling hole with mud to a depth of 40' were 3rd plug was set using 10 sacks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION
3-4-1964
MAR 4 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING & SONS, INC.

Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, LEO F. Dreiling a partner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

(Address)

-SUBSCRIBED AND SWORN to before me this 2nd day of March, 19 64

Notary Public

My commission expires August 14, 1965

WELL LOG

Company **Leo J. Dreiling Oil Company**
 Victoria, Kansas

Sec. 10 Twp. 12 Rng. 16

Farm **Dickinson "D"** No. 1

Location **SW NE SW**

Total Depth **3429'**

County **Ellis County**

Comm. **2/18/64** Comp. **2/25/64**

Elevation: **D. F.**

Contractor **L. J. DREILING & SONS, INC.**
 VICTORIA, KANSAS

G. R.

Casing Record	Cement Record	Production:
8 5/8" - - - 187'	100 sacks cement	D. & A.

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 187	Clay, Rock & Shale
187 - 570	Shale
570 - 680	Sand
680 - 746	Shale
746 - 1019	Red Rock
1019 - 1056	Anhydrite
1056 - 1525	Red Shale
1525 - 1940	Shale
1940 - 2060	Shale & Lime
2060 - 2225	Shale & Lime
2225 - 2505	Shale & Shells
2505 - 2677	Shale & Lime
2677 - 2868	Shale & Lime
2868 - 2938	Lime
2938 - 3062	Lime
3062 - 3130	Lime
3130 - 3212	Lime
3212 - 3300	Lime
3300 - 3392	Lime
3392 - 3429	Lime
3429	TD

RECEIVED
 STATE CORPORATION COMMISSION
 3-4-1964
 MAR 4 1964
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss.
 COUNTY OF ELLIS)

I, Leo F. Dreiling of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report on your Dickinson "D" No. 1.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 2nd day of March, 1964.

Robert Zimmerman
 NOTARY PUBLIC

My Commission Expires: August 14, 1965