


15-051-30040-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 10 Twp. 12 Rge. 16 (E) W (W)  
Location as "NE/CNW&SW¼" or footage from lines SE/NE/MW  
Lease Owner LEO J. DREILING OIL COMPANY  
Lease Name DICKINSON "D" Well No. 3  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 4-17-1965  
Application for plugging filed 4-17-1965  
Application for plugging approved 4-17-1965  
Plugging commenced 4-17-1965  
Plugging completed 4-17-1965  
Reason for abandonment of well or producing formation -0-  
If a producing well is abandoned, date of last production -0- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3375' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	168'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to a depth of 350' with rotary mud and 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 165' where 2nd plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 35' where 3rd plug was set using 10 sacks cement and filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
4-23-1965  
APR 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor L.J. Dreiling & Sons, Inc.  
Address Victoria, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.  
L. Leo F. Dreiling, a partner

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling


LEO F. DREILING VICTORIA, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 21st day of April, 1965

Elmer Weltz  
Elmer Weltz

Notary Public.



L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company LEO J. DREILING OIL CO.  
VICTORIA, KANSAS

Farm Dickinson "D" No. 3

Total Depth 3375'

Comm. 4-9-65 Comp. 4-17-65

Contractor L.J. Dreiling & Sons, Inc.  
Victoria, Kansas

Sec. 10 Twp. 12 Rng. 16

Location SE/NE/NW

County Ellis

Elevation: 1799 D. F.

1804' G. R.

Casing Record

Cement Record

Production:

168' 8-5/8"

125 sax

D&A

Figures Indicate Bottom of Formations

0'	76'	Top soil & post rock
76'	167'	Blue Shale
167'	342'	Shale
342'	516'	Sand & Shale
516'	607'	Sand
607'	749'	Shale & Red Bed
749'	964'	Shale & Red Bed
964'	999'	Anhy.
999'	1420'	Shale & Shells
1420'	1575'	Shale & Shells
1575'	1810'	Shale & Lime
1810'	1961'	Shale & Lime
1961'	2148'	Shale & Lime
2148'	2338'	Shale & Lime
2338'	2536'	Shale & Lime
2536'	2770'	Shale & Lime
2770'	2863'	Shale & Lime
2863'	2933'	Shale & Lime
2933'	3012'	Lime
3012'	3086'	Lime
3086'	3125'	Lime
3125'	3160'	Lime
3160'	3230'	Lime
3230'	3276'	Lime
3276'	3350'	Lime & Cherty
3350'	3355'	Arb.
3355'	3365'	Arb.
3365'	3375'	Arb.
3375'		

RECEIVED  
STATE CORPORATION COMMISSION  
4-23-1965  
APR 23 1965  
T.D.

STATE OF KANSAS)  
ELLIS COUNTY ) ss

CONSERVATION DIVISION  
Victoria, Kansas

I, Leo F. Dreiling, of the L.J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Dickinson "D" # 3.

*Leo F. Dreiling*  
LEO F. DREILING

Subscribed and sworn to before me this 21st day of April, 1965.

My commission expires: October 26, 1968.

*Elmer Kelly*  
NOTARY PUBLIC