

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-04764-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 12 Twp. 12S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NE/4 SE/4 SW/4

Lease Owner Leo J. Dreiling

Lease Name Dreiling "C" Well No. 4

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-29 19 60

Application for plugging filed 4-29 19 60

Application for plugging approved 4-29 19 60

Plugging commenced 4-29 19 60

Plugging completed 4-29 19 60

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3386 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug Hole. First Plug - 450' Twenty sacks cement. Second Plug 160' Fifteen sacks cement. Third Plug 40' - 1/2 sack Hulls Ten sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
5-2-1960
MAY 2 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mast Drilling, Inc.

Address Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Louis M. Mai (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Louis M. Mai

Russell Kansas (Address)

SUBSCRIBED AND SWORN to before me this 30th day of April, 1960

My commission expires July 15, 1964

Notary Public.



15-051-04764-00-00

WELL LOG

OPERATOR: Leo J. Dreiling
Victoria, Kansas

CONTRACTOR: Mast Drilling, Inc.
Russell, Kansas


LEASE: Dreiling C-4
NE/4 SE/4 SW/4
Sec. 12, T12S, R16W
Ellis County, Kansas

COMMENCED: 4-22-60

COMPLETED: 4-29-60

FORMATION	DEPTH
Surface Clay	50
Shale & Shells	169
Shale	280
Sand & Shale	445
Hard Sand & Pyrite	450
Sand	640
Red Bed	987
Anhydrite	1022
Shale	1165
Shale & Shells	1700
Shale & Lime	1920
Lime	2035
Lime & Shale	2340
Shale	2760
Lime & Shale	3060
Lime	3386
TOTAL DEPTH	3386

I hereby certify that the above is true and correct to the best of my knowledge.



 Louis M. Mai

 Louis M. Mai-President

STATE OF KANSAS)

) MAY 2 1960

) 5-2-1960

) CONSERVATION DIVISION

 COUNTY OF RUSSELL) Wichita, Kansas

Subscribed and sworn to before me this 29th day of April, 1960.



Richard L. Mai

 Richard L. Mai-Notary Public

My Commission expires 2-15-64.