

15-051-19242-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 12 Twp. 12 Rge. 16 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SW SW

Lease Owner Leo J. Dreiling Oil Company

Lease Name Dreiling "C" Well No. 1

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed March 9 19 61

Application for plugging filed March 9 19 61

Application for plugging approved March 9 19 61


Plugging commenced March 9 19 61

Plugging completed March 9 19 61

Reason for abandonment of well or producing formation Oil Exhausted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3335' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				10 3/4"	115'	-0-
Oil String				7"	3327'	2404'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand from 3260' to 2740'. Mixed and dumped 4 sacks cement from 2740' to 2720'. Pulled casing to 300'. Mixed and circulated 19 sacks gel mud. Mixed and pumped in 20 sacks cement from 300' to 260'. Pulled casing to 125'. Mixed and pumped in 20 sacks cement from 125' to 85'. Pulled rest casing. Bailed off mud to 25'. Set 5' rock bridge from 25' to 20'. Mixed and dumped 10 sacks cement from 20' to base cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
8-23-1962  
AUG 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pulling Co.

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

I, Leo F. Dreiling a partner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling


(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 62

Ronald J. Zimmerman

Notary Public.

My commission expires August 14, 1965



**WELL LOG**

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec. 12	Twp. 12	Rng. 16
Farm	Dreiling "C" No. 1	Location	SW SW SW	
Total Depth	3335'	County	Ellis County	
Comm.	Comp. Nov. 24, 1952	Elevation:	D. F. 1843'	
Contractor	Salina Drilling Corp. Inc. Salina, Kansas		G. R.	
	Casing Record	Cement Record	Production:	
	8 5/8" - - - 115'	100 sacks cement	Kansas City	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 8-23-1962  
 AUG 23 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 115	Shale
115 - 295	Shale & Shells
295 - 400	Shale
400 - 470	Sand
470 - 515	Hard Sand
515 - 640	Sand & Red Sand
640 - 900	Red Bed
900 - 947	Red Bed
947 - 1000	Anhydrite
1000 - 1135	Shale & Shells
1135 - 1375	Shale & Shells
1375 - 1650	Shale & Shells
1650 - 1725	Lime & Shale
1725 - 1850	Lime & Shale
1850 - 2115	Lime & Shale
2115 - 2305	Shale & Lime
2305 - 2435	Lime & Shale
2435 - 2510	Shale & Lime
2510 - 2730	Shale & Lime
2730 - 2825	Lime
2825 - 2945	Lime
2945 - 3050	Lime
3050 - 3117	Lime & Shale
3117 - 3165	Lime & Shale
3165 - 3255	Lime
3255 - 3345	Lime
3345 - 3640	Lime
3640 - 3659	Lime
3659	TD

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L. J. Dreiling Oil Company upon oath states that the above and foregoing is a true and correct copy of the Daily Drilling Report on the Dreiling "C" No. 1.

*Leo F. Dreiling*  
 LEO F. DREILING  
 LEO J. DREILING OIL COMPANY

Subscribed and sworn to before me this 17th day of August, 1962.

*Ronald Zimmerman*  
 NOTARY PUBLIC