


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

15-051-20812-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 15 Twp. 12 Rge. 16 (E) W (W)  
Location as "NE/CNWKSWK" or footage from lines C-E NE NW  
Lease Owner Dreiling Oil, Inc.  
Lease Name Froelich Well No. 1  
Office Address Rt. #2, Victoria, Kansas 67671  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed 4-3 19 72  
Application for plugging filed 6-19 19 73  
Application for plugging approved 6-20 19 73  
Plugging commenced 7-6 19 73  
Plugging completed 7-6 19 73  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 19 73  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Ks. 67601  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3368 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	198'	
Casing				4 1/2"	3362'	2510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 20 gel w/300 lbs. hulls. Release plug (8/578) and pumped 130 sacks 50-50 Poz 6% gel. 500 Max. Pres. 150# SIP

RECEIVED  
STATE CORPORATION COMMISSION  
7-11-1973  
JUL 11 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.  
Address Box 1082, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Joe Hess, Sec. Treas. of Drlg. Contrc. (employee of owner) or (contractor or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Hess  
JOE HESS, RT. #2, Victoria, Kansas 67671  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 73

Cecilia Basgall  
Cecilia Basgall  
Notary Public.

My commission expires September 13, 1976



15-051-20812-00-00  
**DREILING OIL, INC.**

Victoria, Kansas 67671

**Dreiling Oil, Inc.**

**WELL LOG**

Company **Victoria, Kansas**

Sec. 15 Twp. 12 Rng. 16

Farm **Froelich No. 1**

Location **C-4 1/2 - NE - NW**

Total Depth **3,368'**

County **Ellis**

Comm. **3-27-72** Comp. **4-3-72**

Elevation: **1864** **K. B.**

Contractor **Dreiling Oil, Inc.**  
**Victoria, Kansas 67671**

**1861** **D. F.**

**1859** **G. R.**

Casing Record

198' - 8 5/8"  
3,362' - 4 1/2"

Cement Record

125 sacks cement  
cemented w/125 sacks of  
common cement w/12% salt

Production:

Figures Indicate Bottom of Formations

0'	55'	Soil, Post Rock
55'	115'	Shale- Streaks Sand
115'	198'	Blue Shale
198'	370'	Shale
370'	490'	Sand
490'	850'	Shale & Red Bed
850'	1011'	Red Bed
1011'	1048'	Anhydrite
1048'	1395'	Shale
1395'	1613'	Shale
1613'	1875'	Lime-Shale
1875'	2710'	Lime-Shale
2710'	2855'	Lime
2855'	3368'	Lime
3368'	T.D.	

RECEIVED  
STATE CORPORATION COMMISSION  
6-20-1973  
JUN 20 1973  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS)  
                                  )ss  
COUNTY OF ELLIS)

I, Joe Hess, Secretary Treasurer of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Froelich #1.

Joe Hess  
Joe Hess

Subscribed and sworn to before me this 5th day of April, 1972.

Patty Rohr  
PATTY ROHR NOTARY PUBLIC

My commission expires: July 20, 1975.

