


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

15-051-20837-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 15 Twp. 12 Rge. 16 (E) W (W)
Location as "NE/CNW&SW" or footage from lines SE NW SE
Lease Owner Dreiling Oil, Inc.
Lease Name R.L. Dickinson Well No. 1
Office Address Rt. #2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-25 19 72
Application for plugging filed 7-25 19 72
Application for plugging approved 7-25 19 72
Plugging commenced 7-25 19 72
Plugging completed 7-25 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas 67601
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,425 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	172'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 550' w/70 cu. ft. cement
2nd plug was set @ 180' w/20 cu. ft. cement
3rd plug was set @ 40' w/10 cu. ft. cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.
Address Rt. #2, Victoria, Kansas 67671

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Joe Hess, Sec. Treas. of Drilg. Contrc. (copy to be made and transmitted to the appropriate agency) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Hess
JOE HESS, Rt. #2, Victoria, Kansas 67671
(Address)

Subscribed and Sworn to before me this 27 day of July, 19 72



Patty Rohr
PATTY ROHR
Notary Public.

15-051-20837-00-00
DREILING OIL, INC.

Victoria, Kansas 67671

Dreiling Oil, Inc.		WELL LOG		
Rt. #2				
Company	Victoria, Kansas 67671	Sec. 15	Twp. 12	Rng. 16
Farm	R. L. Dickinson No. 1	Location	SE NW SE	
Total Depth	3,425'	County	Ellis	
Comm.	7-20-72	Comp.	7-25-72	Elevation: 1839
Contractor	Dreiling Oil, Inc.			K. B.
	Rt. #2			1836
	Victoria, Kansas 67671			1834
				G. R.

Casing Record
 172' - 8 5/8"

Cement Record
 125 sacks cement

Production:
 D & A

Figures Indicate Bottom of Formations

0'	50'	Surf. Soil-Clay
50'	172'	Blue Shale
172'	345'	Blue Shale-Clay-Shale
345'	516'	Shale
516'	522'	Hard Sand
522'	700'	Shale & Sand
700'	1061'	Red Bed
1061'	1100'	Anhydrite
1100'	1650'	Shale
1650'	2040'	Shale & Lime
2040'	2255'	Lime & Shale
2255'	2505'	Shale w/Lime streaks
2505'	2905'	Lime & Shale
2905'	3065'	Lime
3065'	3165'	Lime & Shale
3165'	3390'	Lime
3390'	3406'	Lime & Shale
3406'	3425'	Chert.
3425'	T.D.	


RECEIVED
 STATE CORPORATION COMMISSION
 JUL 28 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the R.L. Dickinson #1.

Joe Hess
 JOE HESS

Subscribed and sworn to before me this 27th day of July, 1972.



Patty Rohr
 PATTY ROHR NOTARY PUBLIC

My commission expires: July 20, 1975