


STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 211 No. Broadway  
 Wichita, Kansas

15-051-04359-00-00  
**WELL PLUGGING RECORD**

NORTH



Locate well correctly on above  
 Section Plat

Ellis County, Sec. 15 Twp. 12 Rge. 16 (E) (W)  
 Location as "NE/CNW/SW" or footage from lines NE NE NE  
 Lease Owner Leo J. Dreiling Oil Company  
 Lease Name Dickinson "B" Well No. 1  
 Office Address Victoria, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) D & A  
 Date well completed Nov. 19 1960  
 Application for plugging filed Nov. 19 1960  
 Application for plugging approved Nov. 19 1960  
 Plugging commenced Nov. 19 1960  
 Plugging completed Nov. 19 1960  
 Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3415' Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	161'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Rotary mud was used in filling up hole to a depth of 300' were 1st plug was set using 1/2 sacks hulls and 20 sacks cement, 2nd. plug was set at a depth of 150' using 1/2 sacks hulls and 15 sacks cement, 3rd plug was set at a depth of 35' using 1 sack hulls and 10 sacks cement and filling hole to top.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 8-23-1962  
 AUG 23 1962

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING AND SONS, INC.  
 Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling a partner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
Leo F. Dreiling  
 (Address)

Subscribed and sworn to before me this 17th day of August, 19 62  
Romeal Zimmerman  
 Notary Public.

My commission expires August 14, 1965



L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec. 15	Twp. 12	Rng. 16W
Farm	Dickinson "B" No. 1	Location	NE NE NE	
Total Depth	3415'	County	Ellis County, Kansas	
Comm. Oct. 31, 1960	Comp. Nov. 19, 1960	Elevation:	D. F.	1877'
Contractor	L. J. DREILING & SONS, INC. VICTORIA, KANSAS		G. R.	1875'
	Casing Record 161' - - - 8 5/8"	Cement Record 125 sacks cement	Production:	D & A

Figures Indicate Bottom of Formations


0 - 30	Surface Clay
30 - 161	Shale & Shells
161 - 195	Shale
195 - 300	Shale
300 - 490	Sand
490 - 510	Pryite & Hard Sand
510 - 590	Sand & Shale
590 - 640	Shale & Sand
640 - 1027	Red Rock & Shale
1027 - 1035	Anhydrite
1035 - 1060	Anhydrite
1060 - 1605	Shale & Shells
1605 - 1820	Shale & Shells
1820 - 1965	Shale & Lime
1965 - 2055	Lime
2055 - 2145	Lime & Shale
2145 - 2150	Lime & Shale
2150 - 2275	Shale & Lime Shell
2275 - 2420	Lime & Shale
2420 - 2565	Shale & Lime
2565 - 2700	Shale & Lime
2700 - 2805	Lime & Shale
2805 - 2890	Lime
2890 - 2980	Lime & Shale
2980 - 3120	Lime
3120 - 3171	Lime
3171 - 3250	Lime
3250 - 3285	Lime
3285 - 3410	Lime
3410 - 3413	Lime
3413 - 3415	Arbuckle
3415	TD

RECORDED  
INDEXED  
8-23-1962  
AUG 23 1962

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report on your Dickinson "B" No. 1.

*Leo F. Dreiling*  
\_\_\_\_\_  
Leo F. Dreiling



Subscribed and sworn to before me this 17th day of August, 1962.

*Roman Zimmerman*  
\_\_\_\_\_  
Notary Public