


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-2977-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

ELLIS County. Sec. 16 Twp. 12 S Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines

NE SE SE
Lease Owner Icer Addis
Lease Name CHRISLER Well No. 1
Office Address Box-Drawer 8038 - Wichita, Ks. 67208
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed July 25 19 80
Application for plugging filed July 25 19 80
Application for plugging approved July 25 19 80
Plugging commenced July 25 19 80
Plugging completed July 25 19 80
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3473
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 620' with 70 sacks 50/50 pozmix, 6% Gel thru drill pipe
Middle plug set at 180' w/25 sacks thru drill pipe
top Plug set at 40' w/solid bridge of $\frac{1}{2}$ sack hulls & 10 sacks cement
5 Sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.
BILL DRANEY (employee of owner) or ~~xxxxxx~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of July, 19 80

Shirley M. Hague
Notary Public.

My commission expires April 11, 1982

DRILLER'S WELL LOG

DATE COMMENCED: July 19, 1980
DATE COMPLETED: July 25, 1980

Icer Adlis
CHRISLER #1
NE SE SE
Sec. 16, T12S, R16W
Ellis County, Ks.

0 - 215'	Surface Soil & Shale
215 - 450'	Shale, Sand streaks
450 - 567'	Sand
567 - 573'	Hard Sand
573 - 648'	Shale
648 - 720'	Sand
720 - 1085'	Shale
1085 - 1125'	Anhydrite
1125 - 2864'	Shale & Lime
2864 - 3113'	Lime
3113 - 3117'	Shale
3117 - 3161'	Lime & Shale
3161 - 3405'	Lime
3405 - 3441'	Lime & Shale
3441 - 3473'	Dolomite
	RTD

ELEVATION: 1934 K.B.

FORMATION DATA

Anhydrite	1085'
Topeka	2864'
Hoehner	3113'
Toronto	3131'
Lansing	3161'
Base K.C.	3405'
Arbuckle	3441'
RTD	3473'

Surface Pipe: Set used
8-5/8", 28#, pipe at 206'
w/150 sacks 50/50 po mix,
2% gel, 3% c.c.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.


Bill Draney

Subscribed and sworn to before me this 28th Day of July 1980.

My Comm. Expires:

4-11-1982

Dorothy M. Hoque
Notary Public



RECEIVED
STATE CORPORATION COMMISSIONER
7-29-1980
JUL 29 1980
CONSERVATION DIVISION
Wichita, Kansas