

15-051-01389-00-00
WELL PLUGGING RECORD

OR

Strike out upper line when reporting plugging off formations.

CASING RECORD

[illegible]

filled hole to 130' with heavy
set wood plug at 130' Pump 15' day
Cement mixed heavy for some
filled hole to 20' set wood plug at 20'
Mix & Pump 10' day Cement for some
Cement to Bottom of hole

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Shirley Hogg or
Address: Shirley Hogg

My commission expires. Oct 28, 1948

21-6858-RS 2-47-6M

PLUGGING

FILE REC-18-12 R 16W

BOOK NO. 36 LINE 36

15-051-01389-00-00

W E L L L O G

Hoff #1, Sec. 18-12-16 - Ellis County, Ks.

11-16-45 to
12-10-45

0 to	95	Surface clay & limestone		
95 "	135	Shale		
135 "	640	Shale & shells	2895 to 2920	Shale
640 "	700	Sand	2920 "	3017 Shale & lime
700 "	710	Lime	3017 "	3026 Soft break
710 "	730	Hard sand & pyrite	3026 "	3098 Lime & shale
730 "	942	Sand	3098 "	3203 Lime
942 "	1045	Red bed & shale	3203 "	3223 Lime (hard)
1045 "	1085	Sand, hard	3223 "	3645 Lime
1085 "	1130	Shale & sand	3645 "	3655 Conglomerate
1130 "	1290	Red bed & shells	3655 "	3691 Lime
1290 "	1335	Anhydrite lime		
1335 "	1510	Shale & shells		
1510 "	1785	Shale, shells & salt		
1785 "	1800	Shale & shells		
1800 "	1841	Shale, lime & salt		
1841 "	1990	Lime		
1990 "	2055	Broken lime & shale		
2055 "	2100	Lime		
2100 "	2162	Shale & lime		
2162 "	2280	Lime		
2280 "	2351	Lime & shale		
2351 "	2494	Lime		
2494 "	2535	Lime & shale		
2535 "	2627	Shale & shells		
2627 "	2895	Lime & shale		

3691' Total Depth

Top arb. 3660'

36-36

PLUGGING

SEC 18 T-12 R-16 W

36-36

12-1-1947