

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-27-64

MAR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Clinton Oil Co
Complete Address: 6810 West Highway 54 Wichita, Kansas
Lease Name Berland Well No. 1
Location NE SW NE Sec. 20 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3816
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kansas License No. 436
Operation Completed: Hour 10AM Day 25 Month 3 Year 64

The Above well, was plugged as follows:

~~8 5/8" 181' circulated with cement - 5 1/2" 3815' with 60 sax cement -
Perforated 3762.
Sand back to 3750', set 4 sax cement with dump bailer pulled 2522'
5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550'
(18 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to
200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35',
set bridge and 10 sax cement to bottom collar.~~

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edon Kelly*
Well Plugging Supervisor

3/29/64
8862-u