

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rex & Morris Drlg, Co. Et al

Complete Address: P. O. Box 334 EL Dorado, Kansas

Lease Name Berland Well No. 2

Location NW SW NE Sec. 20 Twp. 10 Rge. 19 (E) (W) XX

County Rooks Total Depth 3790'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Gabbert - Jones, Inc.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 4A Day 29 Month 1 Year 1969

The Above well was plugged as follows:

RTD 3790' 8 5/8 csg set at 207' CWC Gmt. Mat. 50-50 poz Gmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt. thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 1/30/69

INV. NO. 9358-W