

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 25-11  
LOCATION SW SW SE  
SEC. 20 TWP. 10 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Tomascheck

Operator Colorado Oil & Gas Address Box 1030 Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3787 Feet.

Plugging Contractor Bert Self

Plugging Contractor's License No. 48

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 212' circulated with cement - 5 1/2" at 3781' with 100  
sax cement behind.

Chat to 3770', set 4 sax cement with dump bailer, pulled 3000' 5 1/2",  
filled with mud to 210', set rock and 15 sax cement, mud to 40', set  
rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
1-11-56  
JAN 11 1956

CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent  
Date 1-8-56

PLUGGING  
FILE SEC. 20 TWP. 10 R. 19 N  
BOOK PAGE 20 OF 43  
25