

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-2-75
SEP 02 1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zorger Oil Co.

Complete Address 706 Union Natl. Bldg., Wichita, Kansas.

Lease Name Berland Well No. 1

Location SE SW NE Sec. 20 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3764'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor C & G Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 10:45 P Day 30 Month 8th Year 1975

The above well was plugged as follows:

RTD 3764' 8 5/8 csg set 242' cwc 160 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/3/75

INV. NO. 1841-W

Signed: Leo Massey
Well Plugging Supervisor