

15-163-20823-0000

P

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-24-68

RECEIVED  
CONSERVATION COMMISSION  
6-23-78  
JUN 23 1978

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 - 20,823 (of this well)

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center, Wichita, Kansas

Lease Name Berland Well No. 1

Location 370' FSL & 660' FEL of SW/4 NE-NC-SW-SE-SW Sec. 20 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3774'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 5:45 P Day 20 Month 6 Year 1978

The above well was plugged as follows:

RTD 3774' 8 5/8 csg set 216' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6-26-78

INV. NO. 7563-W