

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-29-74
JUL 29 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Shields Oil Producers
Complete Address Shields Bldg., Russell, Kansas
Lease Name Dick Well No. 1
Location NW SW SE Sec. 21 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3750'
Abandoned Oil Well Gas Well Input Well SWD Well D & AXX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.

Operation Completed: Hour 8:30 A Day 26 Month 7 Year 1974

The above well was plugged as follows:

RTD 3750' 8 5/8 csg set at 201' cwc 150 sk. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, displaced 70 sk cmt at 660' thru drill pipe. Heavy
mud to 185' displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74
INV. NO. 9622-W