

15-163-20566-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
6-3-75
JUN 3 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Producers, Inc.
Complete Address Shields Bldg., Russell, Kansas
Lease Name Dick Well No. 2
Location SW SW NE Sec. 21 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3695'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 7 A Day 30 Month 5 Year 1975

The above well was plugged as follows:

RTD 3695' 8 5/8 csg set 216' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 635' thru drill pipe.
Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lee J. Manning
Well Plugging Supervisor

INVOICED

DATE 6/4/75
INV. NO. 1440-w