

R

DISTRICT CONSERVATION AGENT'S REPORT

W

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE-SW-SW

SEC. 26 TWP. 10 RGE. 19-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 111 Lease Smith-Holderman ~~Holderman~~ Holderman

Operator J.A. Allison Address 716 Brown Bldg - Wichita

Field \_\_\_\_\_ County Rooks

Total Depth 3694 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 185 ft. Circulated with Cement  
5 1/2" casing set at 3562 ft & cemented with 125 sacks  
of cement. Filled hole back from bottom to 3340 ft  
Set Plug & 5 sacks cement at 3340 ft above all Preparations  
in the 5 1/2" casing - Shot of & received 2600 ft of 5 1/2" casing  
Filled hole with Mud to 185 ft - Set Plug & 15 sacks cement  
at 185 ft - Surface Plug 20 ft below the surface & 10 sacks  
Cement - Filling hole to Surface - Mud between Plugs.

Jim Baens -  
Pipe Puller & Plugger

C. M. Stouffer  
District Conservation Agent

Date 10-13-47

**PLUGGING**  
FILE SEC 26 T 10 R 19W  
BOOK PAGE 140 LINE 23

A

