

15-163-01124-0002



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sohio Petroleum Company

Complete Address P. O. Box 673, Russell, Kansas 67665

Lease Name Johnson "A" Well No. 1-SWD

Location SW SW SE Sec. 26 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3474'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10 A Day 5 Month 8 Year 1975

The above well was plugged as follows:

Total Depth 3474' 8 5/8 csg set 3037' cwc:

5 1/2 csg set 3466 cwc 1000 sx. No pipe recovered.

Set 5 1/2 wood plug at 2000' -poured 20' sd. Dumped 25' of cem.

Set 5 1/2 wood plug, rock & sd (250-240)

Cutoff 5 1/2 csg at base of cellar & filled 5 1/2 csg & annulus W/readymix cem. to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1975

I hereby certify that the above well was plugged as herein stated. CONSERVATION DIVISION
Wichita, Kansas

Signed: Leo Masarik
Well Plugging Supervisor

INVOICED

DATE 8/8/75

INV. NO. 1742-W