

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
2-14-72
FEB 14 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Johnson "G" Well No. 2

Location SW NW SE Sec. 26 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4 A Day 7 Month 2 Year 1972

The above well was plugged as follows:

RTD 3460' 8 5/8 csg set at 170' cwc. Cmt. Mat. 50550 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/14/72

INV. NO. 5170-21