

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,857 - 0000 (of this well)

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address 200 W. Douglas, Wichita, Kansas

Lease Name Boys Home Well No. 1

Location NE SE NW Sec. 27 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3671'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Big Springs Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 1:15 A Day 18 Month 12 Year 1978

The above well was plugged as follows:

RTD 3671' 8 5/8 csg set 211' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
12-19-78
DEC 19 1978

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bio Massey
Well Plugging Supervisor

DATE 12-26-78

INV. NO. 8801-W