

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
12-8-69  
DEC 8 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Beacon Resources Corp.

Complete Address Suite 1000 Century Plaza, Wichita, Kansas

Lease Name Sutor Well No. 2

Location NW SW SE Sec. 27 Twp. 10 Rge. (E) (W)19

County Rooks Total Depth 3687'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Sage Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 2A Day 4 Month 12 Year 1969

The above well was plugged as follows:

RTD 3687' 8 5/8 csg set at 248' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt

to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo P. Murray  
Well Plugging Supervisor

INVOICED

DATE 12/9/69

INV. NO. 1006-U