


15-163-20250-0000

Form CP-3
Rev. 6-4-68

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1969
CONSERVATION DIVISION
Wichita, Kansas
09-17-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation

Complete Address 1000 Century Plaza Wichita, Kansas

Lease Name O'Brien Well No. 1

Location SE NW NW Sec. 27 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3692

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B - B Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10A Day 15 Month 9 Year 1969

The above well was plugged as follows:

RTD 3692' 8 5/8 csg set at 216' cwc. Cmt. Mat. 50-50 poz cmt W/6%total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/17/69

INV. NO. 489-10

Signed: Geo. J. Mussey
Well Plugging Supervisor