

KANSAS

**STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT**

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address Box 1201 Wichita, Kansas 67201

Lease Name Ruth Largent Well No. 1

Location SE SW SE Sec. 29 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3768'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:45 P Day 16 Month 1 Year 1974

The above well was plugged as follows:

- Total Depth 3765' 8 5/8 csg set at 254' cwc 185 sk.
- 5 1/2 csg set at 3764' cw 175 sk cem.
- 5 1/2 csg PBTD 3700' and perf. (3481-3484)
- Set 5 1/2 wood plug at 3400' -poured 10' sand -dumped 4 sk cem W/dump bailer. (3350-3400)
- Cutoff and recovered 2622' of 5 1/2 csg.
- Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls -70 sk 50-50 poz
- 6% gel. -10 sk gel & water -released 8 5/8 plug and pumped 50 sk 50-50 poz 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED

DATE 1/22/74
INV. NO. 8427-W