

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
7-9-59
JUL 9 1959

CONSERVATION DIVISION AGENT'S REPORT
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

R

File No. 30-20 County: Rooks

Location: SW NW NE Sec. 29 Twp. 10 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3772

I have this date completed supervision of plugging of:

Lease Name: Dick Well No. 2

Operator's Full Name: Petroleum Inc

Complete Address: R#2 Great Bend, Kans

Plugging Contractor: same & Globe Cementing Co

Address: _____ License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1PM Day 2 Month 7 Year 59

The above well was plugged as follows:

8 5/8" at 262' circulated with cement - 5 1/2" 3768' with 100 saxc cement
behind - DV tool at 1607' circulated to top with 265 sax cement and 65 sax
stratocrete - no pipe recovery

Pumped 40 sax mud (Gel) followed by 70 sax cement - hole overbalanced
top of cement at 1316' - filled hole with mud from 1316' to 550',
filled hole from 550' to 0' with cement - open end connection.

Mudding and cementing by Globe Cementing Co.

Signed: *Edon Letty*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 29 TWP. 10 R. 19 W.
BOOK PAGE 30 LINE 20