

15-163-00562-0000

RECEIVED
STATE CORPORATION COMMISSION
7-9-59
JUL 9 1959

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas
R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 30-21 County: Rooks

Location: NE SE NW Sec. 29 Twp. 10 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3752

I have this date completed supervision of plugging of:

Lease Name: Dick Well No. 1

Operator's Full Name: Petroleum Inc

Complete Address: R32x R# 2 Great Bend, Kans

Plugging Contractor: same & Globe Cementing Co

Address: _____ License No. _____

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 1 Month 7 Year 59

The above well was plugged as follows:

8 5/8" at 200' circulated with cement - 5 1/2" 3752' with 100 sax cement -
DV collar at 1550' and hole circulated with cement from 1550' to 0'
with 400 & 150 sax cement - no pipe recovery. PB to 3388', perforated
3362'.

Pumped hole full heavy mud (33 sax Gel), pumped cementing plug followed
by 70 sax cement - cement 560' to 0'.

Mudding and cementing by Globe Cementing Co - 700# to 500# pump pressure.

Signed: *Edwin Lett*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 29 T 10 R 19a
BOOK PAGE 30 LINE 21