

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 3988
Name: Slawson Exploration Co., Inc.
Address: 204 N Robinson, Ste 2300
OKC OK 73102
City/State/Zip: _____
Purchaser: Steve Slawson
Operator Contact Person: _____
Phone: (405) 232 0201
Contractor: Name: Warren Drilling, LLC
License: 33724
Wellsite Geologist: Mike Kiddwell

Designate Type of Completion:

☒ New Well ☐ Re-Entry ☐ Workover
☐ Oil ☐ SWD ☐ SLOW ☐ Temp. Abd.
☐ Gas ☐ ENHR ☐ SIGW
☒ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
☐ Deepening ☐ Re-perf. ☒ Conv. to Enhr./SWD
☐ Plug Back ☐ Plug Back Total Depth
☐ Commingled ☐ Docket No. _____
☐ Dual Completion ☐ Docket No. _____
☐ Other (SWD or Enhr.?) ☐ Docket No. _____
9/30/08 10/12/08 10/13/08
Spud Date or Date Reached TD Completion Date or
Recompletion Date


API No. 15 - 101-22131-0000
County: Lane
NE SE SW 31 18 29 ☐ East ☒ West
935 feet from (S) / N (circle one) Line of Section
2285 feet from E / (W) (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW (SW) 1
Lease Name: RISLEY AB Well #: _____
Field Name: Wildcat
Producing Formation: 2841
Elevation: Ground: _____ Kelly Bushing: _____
Total Depth: 4630 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 319' @ 329' Feet
Multiple Stage Cementing Collar Used? ☐ Yes ☒ No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan P+ A AIT I NR
(Data must be collected from the Reserve Pit) 12-29-08
Chloride content 3500 ppm Fluid volume 9000 bbls
Dewatering method used evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ ☐ East ☐ West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: Operations Mgr Date: 11/6/08
Subscribed and sworn to before me this 6 day of November
20 08
Notary Public: Carl D. Paz
Date Commission Expires: 12-18-08



KCC Office Use ONLY
Letter of Confidentiality Received ☒
If Denied, Yes ☐ Date: _____
Wireline Log Received ☒
Geologist Report Received ☒
UIC Distribution ☒
RECEIVED
KANSAS CORPORATION COMMISSION
NOV 12 2008
CONSERVATION DIVISION

Operator Name: Slawson Exploration Co., Inc. Lease Name: RISLEY 'AB' Well #: 1
 Sec. 31 Twp. 18 S. R. 29 ☐ East ☒ West County: Lane

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☒ Yes ☐ No
 (Attach Additional Sheets)

Samples Sent to Geological Survey ☐ Yes ☐ No

Cores Taken ☐ Yes ☐ No

Electric Log Run ☒ Yes ☐ No
 (Submit Copy)

List All E. Logs Run:

DIL-SP GR - CNL.CDL

☐ Log Formation (Top), Depth and Datum ☐ Sample

Name	Top	Datum
Anh	2178 +671;	B/Anh 2196 +653
Kri	2743 +106;	Wab 3520 -671
Hbn	3919 -1070;	Lns 3962 -1113
Muncie Creek	4141 -1292;	Stk 4246 -1397
Middle Creek	4289 -1440;	BKC 4331 -1482
Marmaton	4373 -1524;	Pawnee 4451 -1602
Uck	4494 -1645;	Ft Scott 4501 -1652
Lck	4526 -1677;	John Z 4563 -1714
Msp	4594 -1745	

CASING RECORD ☐ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surf	12-1/4	8-5/8"	29#	329	60/40	225	2% Gel, 3% CC

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 12 2008

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No	CONSERVATION DIVISION WICHITA, KS
Date of First, Resumerd Production, SWD or Enhr.	Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas

METHOD OF COMPLETION

Production Interval

☐ Vented ☐ Sold ☐ Used on Lease
 (If vented, Submit ACO-18.)

☐ Open Hole ☐ Perf. ☐ Dually Comp. ☐ Commingled

☐ Other (Specify) _____

ALLIED CEMENTING CO., LLC.

32867

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Ness City, KS

DATE 10-13-08	SEC. 31	TWP. 18	RANGE 29	CALLED OUT 2:00 AM	ON LOCATION 6:00 AM	JOB START 11:30 AM	JOB FINISH 12:00 PM
Risler 'AB'	WELL # 1		LOCATION Dighton, Ks SW, 2 1/2 S, 2 1/2 E		COUNTY Lane		STATE Ks
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR	Warren #20
TYPE OF JOB	Rotary plug
HOLE SIZE	7 1/8" T.D. 4630'
CASING SIZE	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	4 1/2" DEPTH 2210'
TOOL	DEPTH
PRES. MAX	200 # MINIMUM 0
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	Freshwater + Mud
EQUIPMENT	

PUMP TRUCK	CEMENTER Rick H.
# 343	HELPER Alvin R.
BULK TRUCK	
# 341	DRIVER Ron H., Kevin W.
BULK TRUCK	
#	DRIVER

OWNER Slawson exploration

CEMENT
AMOUNT ORDERED 255 5x 60/40 4% Gel
1/4# Flo-seal

COMMON	1535X	@ 13.65	2,088.45
POZMIX	1025X	@ 7.60	775.20
GEL	105X	@ 20.40	204.00
CHLORIDE		@	
ASC		@	
Flo-Seal	63#	@ 2.45	154.35
		@	
		@	
KANSAS CORPORATION		@	
COMMISSION		@	
NOV 12 2008		@	
CONSERVATION DIVISION		@	
WICHITA, KS		@	
HANDLING	2685X	@ 2.25	603.00
MILEAGE	2685X X 38 X .10 =		1,018.40
TOTAL			4,843.40

REMARKS:

2210' - 50 sx
1450' - 80 sx
700' - 40 sx
330' - 50 sx
60' - 20 sx - Cement d'd Circulate
Rathole - 15 sx
255 sx 60/40 4% Gel K₄H Fluorol

CHARGE TO: Stawson exploration
STREET _____
CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB 2210'
PUMP TRUCK CHARGE _____ 1170.00
EXTRA FOOTAGE _____ @ _____
MILEAGE 38 _____ @ 7.00 266.00
MANIFOLD _____ @ _____
_____ @ _____
_____ @ _____

TOTAL 1436⁰⁰

PLUG & FLOAT EQUIPMENT

[illegible]

TOTAL

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cement and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME X

SIGNATURE 

ALLIEF CEMENTING CO., LLC. 33258

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Necessity

DATE 10-1-08	SEC. 31	TWP. 18S	RANGE 29W	CALLED OUT 6:30 pm	ON LOCATION 9:30 pm	JOB START 12:00 am	JOB FINISH 1:00 AM
LEASE RISLEY-AD		WELL # 1	LOCATION Dig Hole 5W 2 1/2 S		COUNTY Lane	STATE KS	
OLD OR NEW (Circle one)			W/INTO				

CONTRACTOR	Warren Rig 20
TYPE OF JOB	Surface
HOLE SIZE	12 1/4
CASING SIZE	8 3/8
TUBING SIZE	
DRILL PIPE	4 1/2
TOOL	
PRES. MAX	300
MEAS. LINE	
CEMENT LEFT IN CSG.	20'
PERFS.	
DISPLACEMENT	Fresh Water 19 1/2 BB
EQUIPMENT	

OWNER Stawson Exploration

CEMENT
AMOUNT ORDERED 2255x common +
3% CG + 2% GL

COMMON	<u>225 sx</u>	@	<u>13.65</u>	<u>3,071.25</u>
POZMIX		@		
GEL	<u>5 sx</u>	@	<u>20.40</u>	<u>102.00</u>
CHLORIDE	<u>7 sx</u>	@	<u>57.15</u>	<u>400.05</u>
ASC		@		

_____ @ _____
_____ @ _____
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 12 2008

HANDLING 237 5x @ 2.25 533.25
MILEAGE 237 x .38 x .10 = 900.60

TOTAL 5,007.12

REMARKS:

PIPE ON BOTTOM BREAK CIRCULATION
PUMP 2.25 SX COMMON + 3X CC + 2X GC
SHUT DOWN RELEASED PLUG AND
DISP WITH 19 1/2 BBL OF FRESH
WATER SHUT IN CEMENT DID
CIRCULATE

Rig Down

SERVICE

DEPTH OF JOB	329'		
PUMP TRUCK CHARGE			999.00
EXTRA FOOTAGE	29 Ft	@ 1.80	23.20
MILEAGE	38	@ 7.50	285.00
MANIFOLD	Head Rent	@ 111.00	111.00
		@	
		@	

TOTAL 1,418.20

CHARGE TO: SLAWSON EXPLOYATION

STREET _____

CITY _____ STATE _____ ZIP _____

Thank you

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME X Bill Sheen

SIGNATURE X Ball Ikien

PLUG & FLOAT EQUIPMENT

1-85/8 wooden plug	67.00	67.00
@		
@		
@		
@		

TOTAL 67.00

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS