

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22335-00-00  
Spot: E2SESW Sec/Twnshp/Rge: 16-15S-22W  
520 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: WERTH Well #: 1  
County: TREGO Total Vertical Depth: 4149 feet

Operator License No.: 5663  
Op Name: HESS OIL COMPANY  
Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211	0	160 SX CMT. <b>134.84</b>
T1	3.875	4050		
PROD	5.5	4139	0	150/200 SX CMT.

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/29/2009 9:30 AM  
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY  
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 4% gel - 15 sxs gel spacer - 200# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/29/2009 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 4082' - pumped 15 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1950' cwc with 175 sxs.  
PTOH. Squeezed 5 1/2" casing with 20 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
4139	4142	OH	

INVOICED  
DATE 8-13-09  
INV. NO. 2010060090

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

R. Williams

(TECHNICIAN)

CM

RECEIVED Form CP-2/3

JUN 05 2009

KCC WICHITA

JUN 02 2009

ACT

replacement card

HESS OIL CO  
MCPHERSON KS 67460

16-15S-22W  
140' S, C E/2 SE SW

#1 WERTH

site: 7 N & 2 W OF BROWNELL KS  
 cont: MALLARD JV #1  
 op: JAMES C. HESS

coy: TREGO  
 field: PAGE CREEK NORTH EXT (1/2  
 NE: INFLD DISC)

API 15-195-22335

date 03/08/2006 spd date 03/28/2006 orig comp 04/15/2006 card issued 07/03/2006 last revised 02/26/2007


ELV: 2208 KB, 2203 GL LOG

tops	depth/datum
ANH	1559 - 649
B/ANH	1599 + 609
HEEB	3552 - 1344
TOR	3576 - 1368
LANS	3592 - 1384
STARK	3605 - 1597
BKC	3854 - 1646
PAW	3946 - 1738
FT SC	4032 - 1824
CHER SH	4055 - 1847
CHER SD	4139 - 1931
PBTD	4142 - 1934
RTD	4146 - 1938

IP status:  
 OIL, P 15 BO & 110 BWPD, CHER 4139-4142, 05/17/2006  
 LTD.....4149 -1941

INFO REL: 2/26/2007 - ADDED TOPS & DST  
 NOTE: INFO REL 7/31/2006 - ADDED COMP & MISC INFO  
 CSG: 8-5/8" 211 D 160 SX (ALT 2X 5-1/2" 4139) 350 SX, DV  
 TOOL AT 1521 / 200 SX

COMMENT: PROPOSED START 3/20/2006; MI & RURT  
 3/28/2006; SURF CSG SET, S.D. RIG MAINT UNTIL  
 RESUMING OPERS 4/10/2006

COPYRIGHT 2006  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

(over)

HESS OIL CO  
MCPHERSON KS 67460

16-15S-22W  
140' S, C E/2 SE SW

#1 WERTH

NO CORES

DST (1) 4055-4146 (CHER), / 15-30-15-30, (1ST OP) GB OFF BTM BKT/6", ISI: BLO BK BLDG TO 1-1/4 INCH, (2ND OP) FB OFF BTM BKT/6", FSI: BLO BK BLT TO 1 INCH, REC 840' TF: 240' MC GSY OIL (10% G, 50% OIL, 40% M), 120' GSY OIL (30% G, 70% OIL), 480' FREE OIL ISIP 1271# FSP 1272# IFP 58# -234# FFP 248# -377# IHP 1999# FHP 1896#

TRGT ZN: CHER SD (OIL), PTD 4300 (MISS), MICT (5/2/2006) - CO, PB 4142, (CHER SD OH), SWB DWN, SO, NAT, SET 2-7/8" TBG AT 4050, NO PKR, POP, IPP 15 BO & 110 BWPD (GR 37), DOFP 5/17/2006