

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-30037-00-00  
Spot: S2SWW Sec/Twnshp/Rge: 29-29S-8W  
330 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: RICKARD G Well #: 1  
County: KINGMAN Total Vertical Depth: 4238 feet

Operator License No.: 31714  
Op Name: NOVY OIL & GAS, INC.  
Address: 125 N MARKET STE 1230  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215		
PROD	5.5	4238	1330	137.74

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/28/2009 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: MIKE NOVY Company: NOVY OIL & GAS Phone: (316) 772-1218

Proposed Plugging Method: SAND TO 4150 AND 5 SKS OF CMT. RECOVER CASING. 35 SKS 1250, 35 SKS 775', CIRC CMT FROM 278'-0'

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/28/2009 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4000', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 1330' AND PULLED TO 1250', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 775', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 278', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4181	4198	CSG	

RECEIVED  
JUN 12 2009  
KCC WICHITA

INVOICED  
DATE 8-13-09  
INV. NO. 2010060093

Remarks: ALLIED CMTG COMMON 3% CACL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)