

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01128-00-02
Spot: SESENE Sec/Twnshp/Rge: 19-13S-20W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: LANG Well #: 2
County: ELLIS Total Vertical Depth: 3899 feet

Operator License No.: 30762
Op Name: OIL COMPANY OF AMERICA, INC.
Address: 1200 MAIN STE 101
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	207	0	150 SX
PROD	5.5	3877	0	150 SX

126.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2009 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DARREL HERL Company: OIL COMPANY OF AMERICA, INC. Phone: (785) 625-3800

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 12 sxs gel spacer - 600# hulls.
Perf: 2100' - 1575' - 800' - 175'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2009 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:
Ran tubing to 3720' - pumped 12 sxs gel spacer - followed with 75 sxs cement with 400# hulls.
Pulled tubing to 2100' - pumped 180 sxs cement with 200# hulls - cement circulated.
Pulled tubing out of well - pumped 20 sxs cement down casing.
Max. P.S.I. 500#.
Hooked up to Braden head - pumped 5 sxs cement.
Max. P.S.I. 500#.

Perfs:
INVOICED
DATE 8-13-09
INV. NO. 2010060094

RECEIVED
JUN 15 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38378.
Plugged through: TBG

District: 04 Signed Ray A. Dinkel (TECHNICIAN) CM

JUN 08 2009