

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20721-00-01
Spot: SENWNW Sec/Twnshp/Rge: 3-35S-26W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: WYATT RANCH Well #: 3-1 R
County: MEADE Total Vertical Depth: 6600 feet

Operator License No.: 33392
Op Name: KEITH F. WALKER OIL & GAS CO., LLC
Address: 219 STANLEY ST PO BOX 1725
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6350		WITH 10 SX CMT
CIBP		6460		
SURF	8.625	1520		214.50
COND	16	50		
PROD	4.5	6607	2784	WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/09/2009 9:30 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: PHIL DOLLAR Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 435-3373

Proposed Plugging Method: CIBP @ 6350' WITH 10 SX CMT. PLUG AT 1560' WITH 200# HULLS & 50 SX CMT. PLUG AT 900' WITH 50 SX CMT. PLUG A T360' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2009 10:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 6350' WITH 10 SX CMT. 1ST PLUG LOAD HOLE WITH MUD. PUMP 200# HULLS & 50 SX CMT @ 1560'. 2ND PLUG AT 904' WITH 50 SX CMT. 3RD PLUG AT 355' WITH 50 SX CMT. 4TH PLUG AT 32' WITH 15 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6474	6485		
6398	6410		

INVOICED
DATE 8-12-09
INV. NO. 2010060082

Remarks: USED CLASS A CMT BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JUN 16 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
PIRT II (TECHNICIAN)

RECEIVED

JUN 22 2009

KCC WICHITA

Form CP-2/3