

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24916-00-00
Spot: SWNESWNW Sec/Twnshp/Rge: 5-17S-26W
1910 feet from N Section Line, 905 feet from W Section Line
Lease Name: JOHNSON-DAVIDSON Well #: #1-5
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		WITH 150 SX CMT

149.50

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/07/2009 8:00 PM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL NICHOLS Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 2090' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 640' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE
Date/Time Plugging Completed: 06/07/2009 10:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

1ST PLUG AT 2090' WITH 50 SX CMT. 2ND PLUG AT 1280' WITH 80 SX CMT. 3RD PLUG AT 640' WITH 40 SX CMT. 4TH PLUG AT 260' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED
DATE 8-17-09
INV. NO. 2010060099

KANSAS CORPORATION COMMISSION

JUN 17 2009
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 01

Signed

Jack MacLashy
(TECHNICIAN)

RECEIVED

JUN - 9 2009

KCC DODGE CITY

Form CP-2/3