

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22798-00-00
Spot: NWNENW Sec/Twnshp/Rge: 5-17S-22W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KLITZKE 5B-32D Well #: 1
County: NESS Total Vertical Depth: 4427 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4404		143.88
SURF	8.625	218		WITH 135 SX CMT
DVT		1694		390 SX CIRCULATED TO SURFACE
PROD	5.5	4428	0	WITH 120 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2009 2:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (620) 793-2525

Proposed Plugging Method: MIX 150# HULLS & 35 SX CMT, THEN GEL SPACER TO 1700', THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2009 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG MIXED & PUMPED 200# HULLS & 40 SX CMT, THEN A 19 SACK GEL SPACER, THEN 200 SX CMT. MAXIMUM PRESSURE 600#. SHUT-IN PRESSURE 600#. 2ND PLUG PUMPED 5 SX CMT DOWN 8 5/8" ANNULUS. SHUT IN PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
4303	4307		FORT SCOTT PERF

RECEIVED
JUN 12 2009
KCC WICHITA

INVOICED
DATE 8-17-09
INV. NO. 2010060103

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

MAY 26 2009

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

PKT
Form CP-273