

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21641-00-00  
Spot: SESESE Sec/Twnshp/Rge: 19-25S-4E  
378 feet from S Section Line, 311 feet from E Section Line  
Lease Name: JOHNSON Well #: 1-19  
County: BUTLER Total Vertical Depth: 2910 feet

Operator License No.: 100 <sup>101</sup>  
*KCC state Fee Fund*  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202 *PKT KCC*

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	201		
PROD	4.5	2757		

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2009 8:00 AM  
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/15/2009 11:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WIRELINE INSIDE 2-3/8" FIBERGLASS TBG @ 2460'. POOH W/WIRELINE. WAITED ON LOGGERS. RIH W/WIRELINE @ 2450', SHOT 2-3/8" FIBERGLASS TBG OFF. TRIED TO PULL FIBERGLASS TBG, TBG PARTED 2' DOWN. SDON. 7-14-2009, TRIED TO FISH FIBERGLASS TBG W/OVERSHOT COULD NOT PULL. RIH W/WIRELINE @ 2450 SHOT 2/38" TBG. LAYED DOWN FIBERGLASS TUBING. RIH W/WIRELINE @ 250' AND PERFORATED SQUEEZE HOLES IN 4-1/2" CASING. RIH W/WORKSTRING @ 2400' QUALITY WELL SERVICE MIXED & PUMPED 40 SXS CLASS A 3% CC W/100# OF HULLS AND DISPLACED IN CASING. SDON, 7-15-2009, TAGGED CEMENT @ 1465'. RIH W/WORKSTRING @ 270', QUALITY WELL SERVICE MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN WORKSTRING. RIH W/1" TBG ON BACKSIDE @ 250', QUALITY WELL SERVICE MIXED & PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED OFF CEMENT INSIDE 4-1/2" CASING W/15 SXS. PLUG DOWN 11:30 AM 7-15-2009. QUALITY WELL SERVICE CEMENT TICKET #2324.

Perfs:

Top	Bot	Thru	Comments
2757	2910	OH	

KANSAS CORPORATION COMMISSION  
**AUG 12 2009**  
**RECEIVED**

Remarks: E-20,870. FEE FUND PLUGGING *Control# 2009-0064-001*

Plugged through: TBG

District: 02

Signed *Duane Krueger*  
(TECHNICIAN)

*JK*

*PKT*