

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-10041-00-00
Spot: NENWNW Sec/Twnshp/Rge: 8-30S-8W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: POMEROY Well #: 1
County: KINGMAN Total Vertical Depth: 4245 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 252 | | 200 SX |
| PROD | 4.5 | 4243 | 2100 | 100 SX |

137.96

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2009 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGANSTEN Company: CLARKE CORP Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK 50 FT ABOVE THE PERFS AND 4 SKS OF CMT. RECOVER CASING, 35 SKS 1100', 35 SKS 850', CIRC CMT 300'-O'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/25/2009 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4050', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2100'. THE CASING WAS PULLED FROM THE WELL BORE. TUBING WAS RUN TO 1350', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TO 300', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4116 | 4168 | CSG | |

INVOICED

DATE 8-20-09
INV. NO. 2010060114

RECEIVED

JUL 02 2009


KCC WICHITA

Remarks: ALLIED CMTG COMMON AND 60/40

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

JK

PKT