

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20823-00-00
Spot: NW Sec/Twnshp/Rge: 6-25S-40W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: LEVENS Well #: 1
County: HAMILTON Total Vertical Depth: 2820 feet

Operator License No.: 33573
Op Name: ARENA RESOURCES, INC.
Address: 6555 S LEWIS AVE
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		WITH 180 SX CMT
PROD	5.5	2520	0	WITH 425 SX CMT 91.65

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/29/2009 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RON OSTERBUHR Company: ARENA RESOURCES (CONSULTAN Phone: (620) 272-1232

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2009 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 5 1/2" CASING WITH CMT FROM 2470'-0' USING 200# HULLS & 240 SX CMT.
PRESSURED TO 500# & HELD. FILL 5 1/2" X 8 5/8" ANNULUS USING 10 SX CMT.
PRESSURED TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
464	2470		WINFIELD

INVOICED
DATE 8-20-09
INV. NO. 2010060115

RECEIVED
JUN 25 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

JUN - 9 2009

KCC DODGE CITY

Form CP 2/3