

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20507-00-01
Spot: NWSESWSE Sec/Twnshp/Rge: 21-27S-7W
585 feet from S Section Line, 1955 feet from E Section Line
Lease Name: SCHWARTZ OWWO Well #: 1
County: KINGMAN Total Vertical Depth: 4268 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 532 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	234		200 SX CMT
T1	2.375	3908		
PROD	4.5	4058	2624	100 SX CMT

138.71

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/24/2009 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3850' AND 4 SKS CMT. RECOVER CASING. 50 SKS 1100, 35 SKS 650, CIRC. CMT 284'-0'

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 06/25/2009 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERF WERE COVERED WITH SAND TO 3850', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2624 AND PULLED TO 1100', WHERE 50 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 650', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 284', WHERE CMT WAS CIRCULATED TO SURFACE. 6-25-2009 CMT FELL 215'. COPELAND CAME BACK AND RAN 1.5 POLY TO 210' AND CIRCULATED CMT BACK TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3908	3914		

RECEIVED
JUL 02 2009
KCC WICHITA


INVOICED
DATE 8-20-09
INV. NO. 2010060117

Remarks: COPELAND CMTING COMMON AND 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

