

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-03955-00-00
Spot: SWNE Sec/Twnshp/Rge: 26-18S-10W
4290 feet from S Section Line, 999 feet from E Section Line
Lease Name: ROELFS Well #: 4
County: RICE Total Vertical Depth: 3080 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	221		200 SX
L1	5.5	2572		2572'-3080' <u>100.10</u>
PROD	7	2669		125 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/12/2009 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: JIM MORTON Company: HARTMAN OIL CO., INC. Phone: _____

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/12/2009 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
MIRU, CK BOTTOM. PERFORATE AT 1250' 850', AND 270'. RUN TUBING TO 2558' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 1250' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 850' AND PUMP 50 SX'S CEMENT. LET SET FOR AWHILE AND RUN TUBING BACK DOWN TO 850' AND PUMP 50 MORE SX'S HOT CEMENT. PULL TUBING TO 270' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. PUMPED CEMENT ON BACKSIDE OF 7" AT 150-200#'S. USED 315 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3044	3054	CSG	J ZONE
3006	3009	CSG	H
2882	2885	CSG	B
2572	3080		

INVOICED
DATE 8-20-09
INV. NO. 2010060118

RECEIVED
JUN 25 2009

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35304.
Plugged through: TBG

KCC WICHITA

District: 02 Signed Virgil Clothier
(TECHNICIAN)

✓

PKA