

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20367-00-00
Spot: SENESE Sec/Twnshp/Rge: 1-16S-43W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: EDSALL Well #: 4-F
County: GREELEY Total Vertical Depth: 5260 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2850		
CIBP		5048		WITH 2 SX CMT
SURF	8.625	474		WITH 250 SX CMT 170.95
DVT		2813		WITH 250 SX CMT
PROD	4.5	5267	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2009 9:00 AM
Plug Co. License No.: 34249 Plug Co. Name: SANJEL (USA) INC.
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (719) 340-8987

Proposed Plugging Method: CIBP @ 5048' WITH 2 SX CMT. CIBP @ 2850'. 50 SX CMT FROM 2850-2100'. CIBP @ 2050'. TEST CASING. RUN BOND LOG. PERFORATE IF NECESSARY. RUN TBG TO 2000'. CIRCULATE 4 1/2" FULL OF CMT. CHEC BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2009 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5048' WITH 2 SX CMT. CIBP @ 2850'. PUMP 50 SX CMT AT 2820'. RAN BOND LOG. TOC @ 1400'. TEST CASING & CIBP TO 930#. PERFORATE AT 1300'. INJECTION RATE 4 BPM @ 400# W/NO BLOW ON 4 1/2" X 8 5/8" ANNULUS. PUMP 80 SX CMT, 100# HULLS, & 120 SX CMT. PRESSURE TO 600# & HELD. PUMP 200 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. MAXIMUM PRESSURE 90#. DID NOT GO ON VACUUM.

Perfs:

Top	Bot	Thru	Comments
5108	5111		

INVOICED
DATE 8-20-09
INV. NO. 2010060119

RECEIVED
JUN 25 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SANJEL/

Plugged through: CSG

District: 01

RECEIVED
JUN 10 2009
KCC DODGE CITY

Signed Ken Jehlik
(TECHNICIAN)