

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20414-00-00
Spot: NENWSE Sec/Twnshp/Rge: 1-16S-43W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: EDSALL Well #: F-14
County: GREELEY Total Vertical Depth: 5260 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5050		WITH 2 SX CMT
SURF	8.625	385		WITH 200 SX CMT
DVT		1906		WITH 350 SX CMT
PROD	4.5	5260	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2009 9:00 AM
Plug Co. License No.: 34249 Plug Co. Name: SANJEL (USA) INC.
Proposal Rcvd. from: SHANE PELTON Company: HERMAN LOEB Phone: (719) 340-8987

Proposed Plugging Method: CIBP @ 5050' WITH 2 SX CMT. PERFORATE @ 2770'. PLUG AT 2800' WITH 100# HULLS & 40 SX CMT. CIBP @ 2050'. TEST CASING. RUN BOND LOG. IF NECESSARY, PERFORATE ABOVE TOC & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/02/2009 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5050' WITH 2 SX CMT. PERFORATE @ 2770'. PLUG AT 2820' WITH 40 SX CMT. NO CIRCULATION. SDON. TAG TOC @ 1700'. LOAD HOLE WITH WATER. TEST CASING TO 800# & HELD. RAN BOND LOG. TOC BEHIND 4 1/2" @ 100'. TIH W/TBG TO 1575'. CIRCULATE CMT FROM 1575' TO 0' IN 2 STAGES USING 110 SX CMT. FILL 4 1/2" X 8 5/8" ANNULUS WITH 20 SX CMT. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
5138	5166		

INVOICED
DATE 8-20-09
INV. NO. 2010060119

RECEIVED
JUN 25 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SANJEL.

Plugged through: TBG

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

JUN 10 2009

KCC DODGE CITY