

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20077-00-00
Spot: NENESE Sec/Twnshp/Rge: 32-15S-42W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: PALEN Well #: 2
County: WALLACE Total Vertical Depth: 5250 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1764	0	w/700 sxs cmt
PROD	5.5	5213	0	w/350 sxs cmt <u>170.63</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2009 9:00 AM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB LLC Phone: (618) 943-2227

Proposed Plugging Method: 04/29/2009 - Ordered 420 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Plug through tubing.
06/01/2009 - Ordered 80 sxs 60/40 pozmix - 4% gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2009 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

04/29/2009 - 8 5/8" surface pipe set at 1764' w/700 sxs cement.
5 1/2" production casing set at 5213' w/350 sxs cement.
Production casing had holes. Junk in the hole at 2933'.
Production casing perforated at 2780' and 1730'.
Ran tubing to 2900' - pumped 100 sxs cement with 400# hulls.
Pulled tubing to 2300' - pumped 100 sxs cement with 400# hulls.
Pulled tubing to 1730' - pumped 108 sxs cement.
Cement to surface from 5 1/2" production casing.
Pulled tubing to 865'. Shut 5 1/2" casing valve. Pumped 112 sxs cement.
Cement did not circulate from 8 5/8" surface casing.
Used all 420 sxs cement. Surface and production casing to be topped at a later date.
06/01/2009 - Topped 5 1/2" production casing with 15 sxs cement.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.

Perfs:

Top	Bot	Thru	Comments
5108	5128		
RECEIVED JUN 26 2009 KCC WICHITA			
INVOICED DATE <u>8-20-09</u> INV. NO. <u>2010060119</u>			

Remarks: SANJEL SERVICE COMPANY-TICKET #9134799 AND 9149782.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM


Form CP-2/3

JUN 23 2009

PETROLEUM, INC. 32-15-42W
 300 W. DOUGLAS, #800 #2 PALEN NE NE SE
 WICHITA, KS. 67202

CONTR CHEYENNE DRILLING CTY WALLACE

GEOL TOM ROBERTSON FIELD STOCKHOLM SW



ELV 3878 KB SPD 3/25/86 CARD ISSUED 5/15/86 # P 340 BOPD, NW
3869 GL DRLG COMP 4/3/86 MRW 5108-5128

LOG	Top	Depth/Datum
CO GR	3264 + 614
HEEB	4110- 232
TOR	4135- 257
LANS	4216- 338
KC	4620- 742
CHEH	4726- 848
ATOKA	4866- 988
MRW SH	5011-1133
STOCKHOLM	5102-1224
L MRW LM	5147-1269
STE GEN	5160-1282
PBTD	5154-1276
LTD	5232-1354
RTD	5250-1372

API 15-199-20,077
 8 5/8 " 1764 / 700SX, 5 1/2 " 5213 / 350SX
 NO CORES OR DST'S
 MICT - CO, PF (MRW) 5108-5128, W / 4 SPF, GSO, NAT, POP, P
 340 BOPD, NW (GR 43.8%), 4/11/86

NOTE: CORRECTION: 4/1/86 - ORIGINALLY FIRST REPORTED IN NW NE SE