

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06210-00-00
Spot: NENESW Sec/Twnshp/Rge: 30-18S-7W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MEYER Well #: 6
County: RICE Total Vertical Depth: 3208 feet

Operator License No.: 8917
Op Name: GUSTUS, DEAN DBA JD PRODUCTION
Address: 701 MAIN PO BOX 254
GENESE, KS 67444

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	206		TO TOP
PROD	7	3200		

104.26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/12/2009 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/12/2009 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1100', 700' AND 260'. RUN TUBING TO 3200' AND PUMP 400#'S COTTON HULLS FOLLOWED BY 50 SX'S CEMENT MIXED WITH ANOTHER 100#'S HULLS. PULL TUBING TO 1100' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 700' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

INVOICED
DATE 8/20/09
INV. NO. 2010060120

RECEIVED
JUN 25 2009

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET 5759. COPELAND TICKET #C-35305

KCC WICHITA

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)