

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21203-00-00  
Spot: SENENENW Sec/Twnshp/Rge: 29-15S-10W  
4636 feet from S Section Line, 2702 feet from E Section Line  
Lease Name: CHARVAT-MALIR UNIT Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3272 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3220		
SURF	8.625	325		325 SX <b>106.34</b>
TI	2.875	3215		
PROD	5.5	3272	2120	145 SX CMT.

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/16/2009 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/16/2009 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2760' AND CAP WITH 5 SX'S CEMENT. CUT OFF PROD. CASING AT 2120' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 950' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 375' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3206	3211	CSG	
2983	2988	CSG	
2913	2917	CSG	
2882	2886	CSG	
2863	2868	CSG	
2848	2852	CSG	
2832	2836	CSG	

INVOICED  
DATE 8-20-09  
INV. NO. 2010060121  
RECEIVED  
JUN 25 2009  
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL SERVICE TICKET #3451

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)