

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23870-00-01  
Spot: S2S2SE Sec/Twnshp/Rge: 11-19S-15W  
330 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: CAMPBELL OWWO Well #: 2  
County: BARTON Total Vertical Depth: 3643 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.5	936	0	w/unknown sxs cmt
PROD	4.5	1997	0	w/100 sxs cmt

118.40

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2009 11:00 AM  
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC  
Proposal Rcvd. from: DAVID HAYSE Company: OIL PRODUCERS INC. OF KANSAS Phone: (620) 546-4456

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Flow rate down casing 5 bbls at 275# P.S.I.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 1860' - tied to tubing - pumped 75 sxs cement with 200# hulls.  
Pulled tubing to 1121' - pumped 50 sxs cement with 100# hulls.  
Pulled tubing to 500' - pumped 55 sxs cement - circulated cement to surface.  
Pulled tubing - tied to casing - pumped 10 sxs cement.  
Max. P.S.I. 300#. Shut in.

Perfs:

Top	Bot	Thru	Comments
1834	1838		KRIDER
1808	1824		HERRINGTON

KANSAS CORPORATION COMMISSION

JUN 23 2009

RECEIVED

INVOICED

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

DATE 8/20/09  
INV. NO. 2010060123

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

PKT

JUN 22 2009

OIL PRODUCERS INC OF KS  
WICHITA KS 67208

11-19S-15W  
330' FSL & 1320' FEL, SEC (IRREG)

#2 CAMPBELL OWWO

site: 2-3/4 S & 3-1/4 E OF ALBERT KS	city: BARTON	API 15-009-23870-A
contr: MALLARD JV #1	field: OTIS-ALBERT	
geol:		
fr date 07/23/2001	spc date 08/08/2001	orig comp 08/09/2001
	card issued 12/24/2001	last revised 10/13/2003

		*

ELV: 1962 KB, 1957 GL LOG	
tops.....depth/datum	
HER.....1807 +155	
KRI.....1835 +127	
PBTD.....1950 +12	
TOP.....2935 -973	
HEEB.....3184 -1222	
TOR.....3200 -1238	
DOUG.....3214 -1252	
BR LM.....3265 -1303	
LANS.....3275 -1313	
BKC.....3489 -1527	
CONG.....3503 -1541	
REAGAN SD.....3579 -1617	
RTD OLD.....3643 -1681	

**IP status:**  
**GAS, P & F 200 MCFGPD & WTR, CHASE 1808-1838 OA, 09/17/2001**  
 LTD OLD.....3645 -1683  
 INFO RELEASED: 10/13/2003 - WAS GAS WELL - TIGHT HOLE  
 OLD INFO: OPERATOR WAS ROCKHOUND RESOURCES / THREE-BAR INC, 2 CAMPBELL, SPD 01/20/1985, 01/29/1985  
 8-5/8" 936 (ALT 1), 5-1/2" 3643, OIL, P 17 BO & 15 BWPD, REAGAN 3602-3606 , 09/12/1985(CARD ISSUED 09/19/1985)  
 CONTR: MUSTANG DRILLING & EXPL  
 GEOL: ROD TREMBLAY

COPYRIGHT 2003  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

(over)