

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21778-00-00
Spot: E2NENESE Sec/Twnshp/Rge: 1-15S-27W
2310 feet from S Section Line, 100 feet from E Section Line
Lease Name: CHENEY-FRICKEY UNIT Well #: #1-1
County: GOVE Total Vertical Depth: 4195 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

136.34

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/15/2009 6:00 PM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL Company: PINTAIL PETROLEUM, LTD. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 05/15/2009 10:45 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st. Plug 1775' w/25 sxs.
2nd. Plug at 720' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

KANSAS CORPORATION COMMISSION
JUN 23 2009
RECEIVED

INVOICED
DATE 8/20/09
INV. NO. 2010060125

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

JUN 16 2009

PKT